



RIG

## 850 HP - DRILLING RIG

AC-DC, SCR TYPE, ELECTRIC POWER

850 HP Telescopic Double **RIG TYPE** Care Industries (2011) MAKE DRAWWORKS 1 Detroit Diesel MTU-12V2000 (1000 HP) **AUXILIARY** Eaton 324 brake complete w/ cooling package

**BRAKE** 

MAST Care Industries 105' x 440,000 lb static hook load w/ 10 lines

Care Industries- (18' floor height) Rotary capacity 440,000 lb / Setback capacity 350,000 lb **SUBSTRUCTURE** 

BOP handling system

**TRAVELLING** Warrior - 250 ton **BLOCK** 

**SWIVEL** 

Warrior model 250 hydraulic (250 ton) **TOP DRIVE** 

Drill torque: 25,000 ft x lb

**ROTARY TABLE** 271/2" Hacker 500 ton

**MUD PUMPS** 

Weatherford MP- 10 (1,000 HP) Detroit – 12V2000Weatherford MP- 10 (1,000 HP)

Detroit - 12V2000

2 tank system with complete roof system **MUD SYSTEM** 

Active system: 900 bbl. Five (5) 7.5 HP agitators

Two (2) Shale shakers (King Cobra) One (1) Mud cleaner 3×1 (King Cobra) SOLIDS CONTROL

One (1) Mud D-gasser (MI Swaco)

CENTRIFUGAL Two (2) Badger centrifugal - 5x6x14 c/w 50 HP motors **PUMPS** 2 mix hoppers

Two (2) Badger centrifugal - 6x8x14 c/w 50 HP motors

- mud cleaner

**BOP EQUIPMENT** 

One (1) 13  $5/8" \times 5,000$  psi Shaffer annular One (1) 13  $5/8" \times 5,000$  psi Shaffer SL double gate Two (2) 2  $1/16" \times 5,000$  psi manual gate valves (kill line) One (1) 2  $1/16" \times 5,000$  psi check valve (Kill line)

One (1) 3 1/8" x 5,000 psi manual gate valve (choke line) One (1) 3 1/8" x 5,000 psi HCR gate valve (choke line)

Five (5)  $3\ 1/8" \times 5,000$  psi manual gate valves Eight (8)  $2\ 1/16" \times 5,000$  psi manual gate valves One (1) manual choke valve:  $2\ 1/16" \times 5,000$  psi One (1) hydraulic choke valve:  $2\ 1/16" \times 5,000$  psi CHOKE MANIFOLD

**BOP CLOSING** OCO - 5 station, 120 gallon UNIT

Two (2) Magna Max generators (450 KW each) **POWER** Two (2) Detroit Diesel 60 Series (600 HP each) GENERATION

CCM Distribution

430 bbl (Independent tank) **WATER TANK** 

Two (2) 3x2x11 Mud Hog centrifugal

430 bbl (Independent tank) **FUEL TANK** Two (2) fuel pumps and filtration system **TUBULAR** Six (6) pipe tubs - 2 hydraulic operated One (1) powered catwalk (hands free) **HANDLING** 

Four (4) sets pipe racks

Drill pipe: 250 Joints of the 5" x 19.5 lb/ft - S-135 (4 1/2" IF) **DRILL STRING** 

Drill collars: 18 joints  $6\frac{1}{2}$ " x 4  $\frac{1}{2}$ " XH Drill collars: 8 joints 8" x  $6\frac{1}{2}$ " REG Heavy weight: 40 joints 5" x 4  $\frac{1}{2}$ " IF

As required for drill string **HANDLING TOOLS** 

CASING HANDLING Side door casing elevator for 13-3/8", 9-5/8", 7", 5" TOOLS

Single joints elevators for 13-3/8", 9-5/8", 7", 5 Rotary casing slips for 13-3/8", 9-5/8", 7", 5"

**INSTRUMENTATION** 

Weight Indicator: Martin DECKER Stroke Counter, RPM for RT, pressure gauges Rotary RPM counter and pumps stroke counter

Skidding package to skid rig 150 fee **SKIDDING PACKAGE** Skidding system can go forward to back and side to side

**RIG CAMP** (1) Company Man Unit - Office/Bedroom

(1) Rig Manager Unit - Office/Bedroom

(1) HSE/ Medic Unit (1) Bathroom /Shower Unit

N/A MAIN CAMP

**MATERIAL** One (1) Morooka with Atlas 9,0 ton hydraulic **HANDLING** 

Cimentação Fluidos de Perfuração

> **SERVIÇOS INTEGRADOS** GREATOIL GREATSOLUTIONS

## GREATHOLDINGS

Av. João Cabral de Melo Neto, 400 - Sala 1504

22775-057 .Barra da Tijuca Rio de Janeiro / Rj. Brazil

+55 21 3559-9900